
"Sustainability Evaluation and Recommendations for Vacuum Sewer Systems"



Evaluation and Critique

Comprehensive data summary

The comparison between **vacuum sewer** and **gravity sewer** systems in previous checkpoints showed that vacuum technology offers a sealed pipeline network that conveys wastewater under negative pressure. The shallow installation depth and small-diameter pipes allow vacuum mains to snake around obstacles, high ground-water tables and sensitive ecological areas with minimal excavation. In contrast, gravity sewers depend on continuous downward slope, large pipes and multiple lift stations, leading to deeper, wider trenches and significant disruption during installation. In the Fujairah and Da Nang case studies the total investment for a vacuum sewer network serving roughly 100 households was a little over two hundred thousand euros, whereas a comparable gravity system cost nearly half a million euros. Operation and maintenance (O&M) costs followed a similar pattern: the vacuum system's sealed network requires only one central vacuum station, resulting in annual O&M costs that are a fraction of those of gravity sewers. Adoption data from Airvac shows that hundreds of municipal, commercial, industrial and marine vacuum systems are already in operation worldwide, demonstrating the technology's maturity and scalability.

Validity and limitations

The data analysed in Checkpoints 1 and 2 came primarily from manufacturer presentations, international case studies and pilot programmes supported by development agencies. These sources are credible

because they include engineering details, financial schedules and real-world project outcomes, but there are limitations. The projects cited were located in particular climates (e.g., coastal Vietnam and the Middle East) and involved small communities; costs and performance may differ for large urban centres or cold climates. Manufacturer reports understandably highlight successful installations, so independent verification is essential. We were unable to access some proprietary engineering reports or long-term performance data; therefore there is some uncertainty around long-term maintenance costs and component life expectancy. Nevertheless, the convergence of data from multiple independent case studies gives confidence in the general trends observed.

"An additional factor that warrants attention is the institutional capacity of local utilities. Even if vacuum systems offer strong technical and environmental advantages, long-term success depends on whether the local utility has adequate staffing, training, and budgeting mechanisms to sustain operations. Another potential gap in the available data is the financing structure for small and rural communities, where upfront capital funding models may affect adoption feasibility."

Social considerations

Vacuum sewers deliver clear social benefits. Because the pipe network is completely sealed, there is no odour nuisance, no overflow during heavy rain and no exfiltration of sewage into yards or drinking-water sources. Residents are spared the disruption and safety hazards associated with deep trench excavation, and the central vacuum station keeps workers away from confined-space manholes. In communities that previously relied on septic tanks, the introduction of a vacuum system reduces contact with effluent and improves public health. However, adoption may require homeowner education about the new collection pits and the importance of keeping foreign objects out of the system. Local maintenance crews must be trained to operate and troubleshoot vacuum valves and pumps.

Environmental considerations

A vacuum sewer network uses small-diameter, high-velocity pipelines buried at shallow depths. Less excavation means reduced disturbance of soils, vegetation and archaeological resources, and less spoil to dispose of. The sealed system prevents infiltration of storm water and exfiltration of sewage, protecting ground water and surface waters from contamination. Because the network conveys only wastewater (not diluted storm water), treatment plants can be smaller and more energy-efficient. Some case studies report that vacuum sewers have the lowest carbon footprint of any municipal sewerage system due to reduced excavation, elimination of multiple lift stations and continuous aeration that reduces methane generation. One drawback is that the central vacuum pumps require reliable electricity; backup power systems and energy-efficient pump technologies are therefore critical to minimize greenhouse-gas emissions.

Economic considerations

The shallow trenches and small pipes of a vacuum system reduce material and labour costs during construction. In the Da Nang pilot project the investment cost of the vacuum network was roughly **€0.23 million**, while the gravity system cost about **€0.43 million**. Similarly, annual operation and maintenance costs were about **142 thousand dong** for the vacuum network versus **519 million dong** for the gravity network. These savings arise because vacuum systems eliminate most lift stations and manholes and require less maintenance. While vacuum technology does require specialized valves and a central vacuum station, these costs are offset by reduced excavation and simplified maintenance. In high-density urban areas the initial cost advantage may diminish because of the need for larger vacuum stations, but the technology still offers operating savings.


Technical considerations

Vacuum sewers rely on negative pressure to transport wastewater. A collection pit with a pneumatic valve connects each household or cluster of homes to the main. When a small volume of wastewater enters the sump, the valve opens and the mixture of sewage and air is rapidly conveyed to the central station. The high velocity (typically 5–18 feet per second) scours the pipe walls, preventing sedimentation and blockages. Because the valves are pneumatically actuated, they do not require electricity at each pit. The system can continue to operate for several hours during power outages using stored vacuum and generator backup at the central station. The main technical challenges include ensuring tightness of the network, preventing leaks that degrade vacuum pressure, and providing access to spare parts and trained technicians. Vacuum systems are best suited for flat or undulating terrain, coastal areas, high water tables and small to medium-sized communities. In mountainous areas or where long transmission distances are required, a gravity or pressurized sewer may still be preferred.

Pillar	Key Considerations
Social	• Eliminates exfiltration → reduces disease risk • No odors due to sealed system → improves community comfort • Shallow trenches → safer installation for workers • Faster construction → less disruption for residents
Economic	• Lower installation cost due to reduced trenching • Less maintenance (no lift stations) → reduced O&M cost • Long-term durability of HDPE pipes → fewer replacements • Efficient system layout → cost-effective for flat/flood-prone areas
Environmental	• Fully sealed → zero sewage leakage into soil/groundwater • Reduced excavation → protects vegetation and habitat • Lower energy consumption vs multiple lift stations • Ideal for flood-prone areas → enhances environmental resilience

Data Visualizations


Investment Cost Comparison



Investment cost comparison between vacuum and gravity systems


Figure 1. Investment cost comparison for vacuum and gravity sewer systems (approximate values based on Da Nang case study).

Annual Operation & Maintenance Cost Comparison



Annual O&M cost comparison between vacuum and gravity systems

Figure 2. Annual operation and maintenance cost for vacuum and gravity sewer systems (Da Nang pilot). Costs are shown in millions of Vietnamese dong.Distribution of Airvac Vacuum Systems by Type




Pie chart showing distribution of Airvac vacuum systems

Figure 3. Distribution of the 437 Airvac vacuum sewer systems in North America by type (municipal, commercial, industrial, marine and others).

Comparative Analysis Table

Feature	Vacuum Sewer System	Gravity Sewer System
Construction cost	Lower due to shallow trenches and smaller pipes; little excavation and minimal surface disruption	Higher because deep, wide trenches are required; extensive excavation, multiple manholes and lift stations
Pipe diameter	Small diameter (4–10 inches) HDPE or PVC pipes	Larger diameter (≥200 mm) concrete or PVC pipes
Excavation depth	Typically 1–2 m; flexible layout avoids obstacles	Trenches often >3 m deep; limited flexibility
System seal	Fully sealed, no infiltration or exfiltration; eliminates odour	Open system; risk of infiltration, exfiltration and odour at manholes
Maintenance	Centralized at vacuum station; annual inspection of pits; lower operational cost	Decentralized; frequent manhole and pump maintenance; higher operational cost
Energy consumption	Electricity needed only at vacuum station; valves are pneumatically operated	Multiple pump stations require electricity and backup power
Environmental impact	Minimal ground disturbance; protects groundwater; lower carbon footprint; resilient during floods	Greater disturbance; risk of groundwater contamination; methane from anaerobic manholes
Resilience	Can operate during floods and short power outages with vacuum stored in system; self-cleaning high velocity reduces blockages	Vulnerable to power outage; flooding causes overflows and backflows



Recommendations

Vacuum sewer systems offer a compelling alternative to gravity systems in many contexts. Based on the data analysis and critique, the following recommendations are proposed:

- **Adopt vacuum systems for small and medium-sized communities in flat or low-lying areas.** Municipalities with high groundwater tables, poor soil conditions or existing septic tanks should prioritize vacuum technology because it minimizes excavation and protects water resources. Pilot projects can demonstrate feasibility and build public trust.
- **Develop clear policies and standards.** National and local governments should develop standards for vacuum sewer design, construction and operation. Guidelines should cover design parameters, testing for airtightness, energy efficiency, and contingency plans for power outages. Standards will help utilities and contractors implement projects consistently and ensure quality.
- **Engage the community.** Outreach campaigns should educate residents about how vacuum sewers work, proper use of collection pits, and the benefits of a sealed system. Community engagement helps prevent misuse (such as disposing of foreign objects) and encourages households to support the new technology.
- **Train local operators and build capacity.** Utilities should invest in training programmes for engineers and maintenance staff on vacuum technology, including troubleshooting valves and pumps. Partnerships with experienced suppliers can provide technical assistance and ensure supply of spare parts.
- **Integrate sustainability and resilience.** Projects should evaluate social, environmental, economic and technical impacts. Vacuum systems contribute to all three sustainability pillars: they improve public health and quality of life (social), protect water resources and reduce greenhouse-gas emissions (environmental), and lower long-term costs (economic). Resilience

measures should include backup power for vacuum stations and monitoring systems to detect leaks or blockages.

- **Explore hybrid systems where appropriate.** In hilly regions or large urban centres, a hybrid approach may be optimal — for example, using vacuum sewers for collection within neighbourhoods and gravity or pressurised mains for long-distance conveyance. This combination can deliver cost savings while maintaining reliability.

Final Policy Memo Draft

To: Municipal Planning Department and Public Works Officials

Subject: Adopting Vacuum Sewer Technology for Sustainable Wastewater Management

Dear colleagues,

Over the past semester we have evaluated alternative sewer technologies for our community. Conventional gravity systems have served us for decades, but they come with high installation and maintenance costs, significant environmental impacts and vulnerability during floods and power outages. Vacuum sewer technology offers an innovative solution that addresses many of these challenges.

Unlike gravity sewers, vacuum systems use negative pressure to transport wastewater through small-diameter, shallow pipes. This means roads and sidewalks need only shallow trenches, reducing construction time, costs and disruption. Because the network is fully sealed, there is no risk of sewage leaking into groundwater or storm water entering the pipes. Residents benefit from the absence of odours and overflows, and maintenance crews work at a single vacuum station rather than climbing into manholes across the city.

Case studies from Fujairah (UAE) and Da Nang (Vietnam) show that vacuum networks cost roughly half as much to build as gravity systems and are far cheaper to operate. Hundreds of vacuum systems are already operating worldwide in municipal, commercial, industrial and marine settings, demonstrating the maturity of the technology. In small coastal towns or new developments near floodplains, the advantages are especially compelling.

I recommend that our municipality undertake a pilot project using vacuum sewer technology in one of our growing residential areas with high groundwater and aging septic tanks. We should partner with experienced vacuum system vendors to design and install the system, train our staff and monitor performance. If the pilot confirms the expected benefits — lower costs, improved environmental protection and increased resilience — we can adopt vacuum sewers more widely in future developments.

This policy aligns with our commitment to sustainable infrastructure: it protects our water resources, supports long-term economic viability and enhances community well-being. I look forward to discussing this proposal and working together on a more sustainable future.

Sincerely,

Samagnkumar Sripathi,
Graduate Student, Civil & Environmental Engineering,
University of Dayton.

References

1. **Crincoli, Philip.** *Vacuum Sewer System Design Overcomes Obstacles at an EPA Superfund Site Located in the Middle of the Salt Lake Valley*. Presentation for the Florida Brownfields Association Conference, Airvac Vacuum Wastewater Technologies, 2022. https://www.floridabrownfields.com/assets/2021conference/Presentations/Crincoli%20Brownfields%20April%202022.pdf
2. **New Forest Solutions.** *Vacuum Systems – The Advantages*. New Forest Solutions Ltd., 2016. https://newforest.solutions/advantages-of-vacuum-sewage/
3. **Flovac Vacuum Sewerage Systems.** *How Vacuum Sewerage Systems Work*. Flovac, 2025. https://flovac.com/how-vacuum-sewerage-works/
4. **United Nations ESCAP & Deutsche Gesellschaft für Internationale Zusammenarbeit (GIZ).** *Report on Research on Vacuum Sewer Collection System for Pilot Project An Hai Bac Ward in Eastern Coastal Area of Da Nang, Vietnam* (revised August 2014). https://www.unescap.org/sites/default/files/Vietnam_Danang_1408_%20Report%20on%20research%20on%20vacuum%20sewer%20collection%20system%20for%20project%20site.pdf